



MEMORANDUM OF AGREEMENT

Name	abc
Address	Lucknow
Mobile	1234567890
Subject	Quotation for the construction of Residence at Madhav green, Lucknow

Dear Sir/Mam,

“The Work” according to drawing and details, showing description of the work to be done under the direction of the client approved by the Architect.

SCOPE OF WORK:

A. STRUCTURE

As per Approved Drawings. Frame Structure, R.C.C. Slab (Slab thickness and steel as per structure drawing or as per Architect), super structure brickwork 4.5 inch.

B. CIVIL WORK (MATERIAL)

Coarse sand: First class.

Cement: Ultratech, Prism.

Brick: 1st class.

Reinforcement: Gallant, RHL.

C. PLASTER WORK

Inside plaster on walls.

Elevation plaster on walls.





D. INTERNAL PLUMBING / DRAINAGE WORK

Drainage/Down Pipes of PVC (Astrol, Supreme) as required.

CPVC (Astrol, Supreme) pipes for water supply as specified.

Inspection Chambers, Manholes and gully traps etc. as per drawing.

Toilet seat fixtures and fittings of Cera, Parryware or equivalent, Economical range.

W.C.: 1. Wash basin: 1 without platform. Tap: 1; Diverter or L band.

E. INTERNAL ELECTRICAL WORK

Conduct PVC pipe + Band of medium grade of ISI make Polycab, Cap.

Junction box, Fan box: Iron, Deep box: C.I.

Wire: RR Cable, Polycab, Anchor.

Switches: RR Cable, Polycab, Anchor.

Inverter Wiring.

F. FLOORING (TILE)

Bathroom tiles: Kajaria (1 × 1.6 feet).

Floor tiles: Kajaria (2 × 4 feet).

Wall tiles in bathroom (height 7 feet).

Kitchen marble.

Tiles: only 2 feet high above the counter.

G. DOOR AND WINDOW

Only outer door and windows will be of double patam.

All doors will be of ISI marked Flush Doors.

Bathroom door will be of waterproof flush door.

Window frame will be of sagwan wood with 4 mm glass.

Main door with interlock will be provided.

H. PAINTING (PUTTY)

For interior: Nerolac, JK, Bajaj wall putty 2 coats.

Pop design: in all room.





False ceiling: only in drawing room.

For Exterior: Apex ultimate of Berger paint. Colour as per Architect and Client's Choice.

I. CHAUKHAT

Chaukhat: Malasyian Sakhu.

Door Frame and window Frame: Malasyian Sakhu.

J. IRON WORK

GRILL WORK: On windows.

Railing to be made of SS Steel.

STAIRCASE of stainless steel.

OTS jall in MS.

Main gate (₹25000).

K. FEE CHARGABLE:

The Total fee chargeable for the above mentioned services is calculated on super built-up area:

Ground floor: 1000 sq ft × ₹1,700.00 = ₹17,00,000.00

Base cost: ₹17,00,000.00

Main gate: ₹25,000.00

Priced extras: ₹0.00

Subtotal: ₹17,25,000.00

Total cost: ₹17,25,000.00

NOTE: The area mentioned in agreement are based on drawings prepared. Final area may vary as per site. Final calculation will be done as per site measurements on actual basis.

TERMS & CONDITIONS

Electricity & water supply to be provided by client before commencement of work.

Any extra work outside the covered area will be calculated on item rate.

Arrangement of water and light on the site by owner before commencement of work.

Following items will be charged extra if required by client. Any extra work will charged separately and the cost of these items are not included in the covered area rates.

Staircase has double measurement area.

Tax will be charged 18% extra in case of payment in account.

In case of late payment 10% penalty charged on amount.





EXTRA WORK:

Texture paint / wallpaper — charged separately if required
Soil — charged separately if required
Septic tank — charged separately if required
Modular kitchen — charged separately if required
Concealed lights, tubelights — charged separately if required
Parapet or boundary wall — charged separately if required (₹225.00 / sq ft)
Earthing for electrical — charged separately if required
Demolition — charged separately if required. Charge as per site condition
Elevation tile — charged separately if required

PAYMENT CONDITION

Payment base: total including tax, ₹17,25,000.00.
Advance: 30% — ₹5,17,500.00
After DPC / brickwork: 20% — ₹3,45,000.00
After shuttering, before slab: 30% — ₹5,17,500.00
After plaster: 10% — ₹1,72,500.00
Finishing: 10% — ₹1,72,500.00

ADARSH
INFRADEVELOPERS & CONSTRUCTIONS





For,
Adarsh Infradevelopers and Construction

Accepted by
abc

Signature

Name & Signature

1- Witness:

2- Witness:





ADARSH INFRADEVELOPERS AND CONSTRUCTIONS



Contact- 9453919659, 7905443687

Address - 1/69 Sec 1 Gomti Nagar, Lucknow 226010

<https://adarshinfra.co.in/>

E-Mail: adinfra.cont@gmail.com



- Adarshinfra.co



- Adasrh Infradevelopers and constructions